

BID PRICES/ BILL OF QUANTITIES FOR THE PUBLIC BIDDING OF: **UPLB-I-036-7-17 SUPPLY, DELIVERY AND INSTALLATION OF AIRCONDITIONING UNITS FOR OVCPD**

DATE OF SUBMISSION OF BIDS:

Thursday, 31 August 2017 1:15 PM

UNIT/ END-USER	LOT #	ITEM #	PARTICULARS	QUANTITY	UOM	APPROVED BUDGET		BIDDER'S OFFER	
						UNIT COST	TOTAL COST	UNIT PRICE	TOTAL PRICE
OVCPD FC: 9305710	1	1	Supply, delivery, installation: air-conditioning unit, brand new, 2.0 HP basic inverter wall mounted split type aircondiitoning unit, cooling cap. KJ/HR 9,200-18, 750 EER 14.7-12.3, amps 2.30-8.47, watts 625-1, 520, volts 230, Hz60, 1 phase wireless remote control R410A	2	UNITS	67,767.575	135,535.15		NO OFFER
			including installation cost of labor and materials with supervision, scope of work as follows:						
			1. fabricate mounting frame using angular bat 3/16" x 1 1/2" pre-painted for ACCU						
			2. layout/fixing of copper pipe using 1/2" gas line and 1/4" liquid line hard drawn type-L, electrical control line stranded wire THHN 3.5mm ² , main line 5.5mm ² , circuit breaker 30 amps, nema 3R drainage line eslon blue pipe 1/2" dia., including insulation rubber hose 3/4" thickness wall with vinyl tape insulation						
			3. system flushing, leak testing, vacuuming						
			4. refrigerant charging R410A						
			5. start up and commissioning						
			6. attach certificate of warranty						

BID PRICES/ BILL OF QUANTITIES FOR THE PUBLIC BIDDING OF: **UPLB-I-036-7-17 SUPPLY, DELIVERY AND INSTALLATION OF AIRCONDITIONING UNITS FOR OVCPD**

DATE OF SUBMISSION OF BIDS:

Thursday, 31 August 2017 1:15 PM

			TOTAL FOR LOT 1=			135,535.150		TOTAL BID FOR LOT 1	-
OVCPD	2	1	Brand new inverter 3.0HP ceiling mounted split-type airconditioning cooling capacity (3,200-27,000) BTU/H 24,200 watts 2,530, EER 10.1, 220 volts, 60 Hz, 1 phase, wireless remote control R410A	1	set	109,800.000	109,800.00		
	2	1	Installation cost of labor and materials with supervision, scope of work as follows:	1	lot	24,012.450	24,012.45		
			1. Fabricate mounting frame using 3/16" x 1 1/2" for indoor unit and outdoor unit, pre-painted layout-/fixing						
			2. Layout/fixing of copper pipe using 5/8" gas line and 3/4" dia. Thickness rubber insulation, electrical control line stranded wire thhn 3.5mm ² , main line 5.5mm ² , circuit breaker 40 amps, nema 3R, enclosure, drainage line pipe line ESLON BLUE 3/4" dia., including vinyl tape insulation						
			3. System flushing, leak testing, vacuuming, charging						
			4. Refrigerant charging R410A						
			5. Start up and commissioning						
			6. Attach certificate of warranty						
			TOTAL FOR LOT 2=			133,812.450		TOTAL BID FOR LOT 2	-
						GRAND TOTAL:	269,347.60	Total Bid:	-

BID PRICES/ BILL OF QUANTITIES
ENVELOPE "B"

BID PRICES/ BILL OF QUANTITIES FOR THE PUBLIC BIDDING OF: **UPLB-I-036-7-17 SUPPLY, DELIVERY AND INSTALLATION OF AIRCONDITIONING UNITS FOR OVCPD**

DATE OF SUBMISSION OF BIDS:

Thursday, 31 August 2017 1:15 PM

Total Approved Budget for the Contract:	PHP 269,347.60
Required Bid Bond (2% of the ABC):	PHP 5,386.95
Required Bid Bond (5% of the ABC):	PHP 13,467.38
Contract Duration:	30 CD upon receipt of notice to proceed
Price Validity:	120 calendar days from bid opening
TOTAL BID PRICE (in figures):	<u>PHP 0.00</u>
TOTAL BID PRICE (in words):	
Company Name:	
Address:	
Phone No.:	
Fax No.:	
E-mail Address:	
Quoted by (Name and Signature):	