

THE PUBLIC BIDDING OF:  
 SUBMISSION OF BIDS:

**UPLB-I-045-12-17 SUPPLY, DELIVERY AND INSTALLATION OF AIRCONDITIONING UNITS FOR OVCPD**  
**Monday, 11 December 2017 1:00PM**

LOT #	ITEM #	REQUIRED SECIFICATIONS	OFFERED SPECIFICATIONS (write down detailed offered specifications)	REFERENCES (include supporting documents)	COMMENTS/ REMARKS (clarify inclusion/ exclusion)	EVALUATION
		<b>AIRCONDITIONING UNITS FOR OVCPD</b> <b>(For ABD Faculty Office at 2nd floor NCAS Annex 1)</b> <b>FC: 8236200</b> <b>RCC: LB02010001-C0001417</b> <b>End-user: Ms. Cleofe O. Manatac</b>				
2	1	2 sets of Brand new inverter 3.0 HP ceiling suspended split-type airconditioning unit model equivalent to #CS-T24KTQ6 indoor, CU-YT24KBQ6, outdoor, side discharge, cooling capacity KJ/H 25,560, BTU/H 24,200, amps 11.7, KW 2.53, EER 10.10, 220-240 volts, 60HZ, 1 phase, wireless remote control R410A				
2	2	Installation Cost of Labor and Materials with supervision for 2 A/C Units				
		<i>Scope of work to be done:</i>				
		A) Fabricate mounting frame using 3/16" x 1 1/2" angular bar for ACCU and FCU, pre-painted				
		B) Layout/fixing of copper pipe using 5/8" gas line and 3/8" liquid line hard drawn type-L, electrical control line stranded wire thhn 3.5mm <sup>2</sup> , main line 5.5mm <sup>2</sup> , circuit breaker 30 amps. Nema 3R, enclosure, drainage line 3/4" eslon blue pipe, rubber hose insulation 3/4" thickness wall with vinyl tape insulation				
		C) System flushing, leak testing, vacuuming, charging				
		D) Refrigerant charging R410A				
		E) Start up and commissioning				
		F) Attached warranty certificate				
		G) Site inspection is a must				

Note: Please fill-up applicable columns.

Signature of Representative: \_\_\_\_\_

Name of Representative: \_\_\_\_\_

Position: \_\_\_\_\_

Company: \_\_\_\_\_

Address: \_\_\_\_\_

Telephone/ Fax: \_\_\_\_\_

Email: \_\_\_\_\_

End-user:

\_\_\_\_\_  
 Signature over Printed Name