UPLB BAC SECRETARIAT
BY: [illegible] DATE: 3-8-2023

MAR 13 2023

UPLB-RQ-
UPLB-RQ 3-019-23-I - Nam
DEADLNE OF SUBMISSION

UNIVERSITY OF THE PHILIPPINES
LOS BANOS
Los Banos, IV-A
VAT Reg. TIN: 000-864-006-00004

Request for Quotation/ Bid Form (Technical Specifications)
INSTITUTE OF CHEMISTRY

Suppliers Name _____

Date: 01 March 2023
Fund Code: N83152A
MOP: SMALL VALUE PROCUREMENT
Contact No: 9057385975
Contact Person: Angel S. Ancheta

Please quote your lowest price on the item/s listed below, subject to the General Conditions below.

Note:
1. Bidders shall provide correct and accurate information required in this form. All entries must be typewritten or in print and properly accomplished. Do not leave blank entries, put N/A for not applicable.
2. Price quotation/s to be denominated in Philippine Peso shall include all taxes, duties, and/ or levies payable.
3. Bidders must indicate the BRAND and MODEL NUMBER for equipment and its accessories or peripherals. Evidence shall be in the form of manufacturer's un-amended sale literature, unconditional statement of specification
4. Quotation through fax/email is acceptable. Winning bidder shall submit original signed RQ before issuance of Puchase order (P.O.).
5. Quotations exceeding the Appoved Budget for Contract shall be reiected.
6. Documentary requirements per Memorandum No. 03 Series of 2017 shall be attached upon submission of the quotation.
7. Others:

ITEM No.	GENERAL NAME OF THE ITEM	REQUIRED SPECIFICATIONS	UNIT OF MEASURE	QTY	ESTIMATED UNIT APPROVED BUDGET OF THE CONTRACT	ESTIMATED TOTAL APPROVED BUDGET OF THE CONTRACT	OFFERED SPECIFICATION Suppliers must state here the detailed technical specifications of their offer against each of the individual parameters of each	QUOTED UNIT PRICE	TOTAL QUOTED PRICE	EVALUATION (Leave this space blank. For BAC/ Evaluators only)
	Inverter Spilt Type Air Conditioning Unit with Supply/Delivery, Labor & Materials including Installation	**SPECIFICATION:** Brand new 5.0 HP Full DC Inverter type Ceiling Suspended Split Type Airconditioning Unit with Rated Cooling Capacity 42,700 (13,000-43,300) BTU/hr, Power Input 4.42 (1.30-4.80) KW., EER 9.66 Power Source, 230 Volts, 60Hz, 1 Phase, Running Current (26 Max Amps) R410A Refrigerant, Pipe diameter liquid side 3/4", Gas side 5/8" O.D. Wireless Remote, at least 1 yr warranty on parts and services	lot	1	**270,000.00**	270,000.00				
		SCOPE OF WORK								
		A. Layout and installation of fabricated angle bar 3/16" x 1 1/2" thickness, pre painted primer epoxy (gray) for FCU and ACCU								
		B. Mounting and Installation of Air Conditioning units FCU and ACCU with Rubber Pad Support.								
		C) Chipping and Plastering of Concrete or Glass								
		D) Layout and Installation of Drainage Pipeline using PVC 3/4" Diameter (Eslon Blue)								
		E. Layout and Installation of Electrical PVC (Neltex) Including Power and Transmission Wirings from FCU to ACCU using 3.5mm2 Including Grounding Line								
		F. Layout and Installation of Electrical Wiring 5.5mm? and Liquid Tight Flexible Conduit with Connector from ACCU to 50 amp. Circuit Breaker NEMA 3R Enclosure | meter from ACCU)								
		G. Layout and Installation of Hard Drawn Copper Pipe 5/8" O.D. And 3/8" O.D. Type -L with Rubber Insulation 3/4%" thickness from FCU to ACCU including Vinyl tape Insulation								
		H.Leak Testing and Correction, System Flushing and Vacuuming								
		I.Refrigerant Charging and Start Up with Commissionin.								
		J. Provision/Metal Cladding of Refrigerant Pipe sets from ACCU to FCU, using galvanize iron guage 0.5mm as per drawing 1" x 3"x.4" size (Pre-painted same as Wall Painted)								
		K. Attach Certificate of warranty								
		COPPER PIPE AND FITTING WITH INSULATIONS								
		20 Ft. Copper Pipe 7" O.D. x 1.02mm THK Type -L Hard Drawn								
		20 Ft. Copper Pipe %" O.D. x 0.76mm THK Type -L Hard Drawn								
		4 Pes. Copper Elbow % " LD. x 90° Long Radius								
		4 Pcs. Copper Elbow %" LD. x 90° Long Radius								
		5 Pcs. Flat Silver Rod 18"								
		4 Length |Elastomeric Rubber Insulation % " 1.D. x %" THK x 6								
		4 Length |Elastomeric Rubber Insulation %" LD. x %" THK x 6'								
		2 Rolls |Polyethylene Vinyl Tape Insulation 4" x 50 meters								
		ELECTRICAL WORK FOR ACCU TO FCU, CONTROL WIRINGS, CONDENSATE DRAIN								
		1 Set Circuit Breaker 60 Amps. 2 pole, Bolt on Type, NEMA Enclosure								
		32 Mtrs. |THHN Stranded Wire #3.5 mm2								
		6 Mtrs. |THHN Stranded Wire #8.0 mm2								
		4 Length |PVC Pipe Y," dia X 10' (Neltex)								
		7 Pcs. PVC Long Elbow 2" x 90° (Neltex)								
		2 Mtrs.|Liquid Tight Electrical Flexible Hose 4" dia. (Soft)								
		2 Pes. Liquid Tight Straight Connector 72" dia.								
		4 Length |PVC Pipe 34." dia x 10' (Eslon Blue)								
		6 Pes. PVC Elbow %" dia X 10' (Eslon Blue)								

		STEEL FRAME / METAL CLADDING SUPPORT FOR ACCU AND FCU						
		2 Length |Angle Bar 3/ 16" x 1½" x 20' Feet						
		1 Klg.. Welding Rod						
		8 Pes. Bolt & Nut with Flat/lock Washer ½" dia x 2" long						
		11 Pcs. Expansion Shield ¼,"dia x 2½" Galvanized bolt Screw						
		1 Sheet |G_I. Plain Sheet 4'x8' x 0.5mm (for Cladding Materials)						
		60 Pes. Plastic Tox with Metal Screw (6mm)						
		REFRIGERANT SYSTEM FLUSHING, LEAK TESTING, VACUUMING,CHARGING						
		4 Klgs. |Refrigerant R4 10A						
		OTHERS CONTINGENCY TO COMPLETE THE INSTALLATION						
		Mapp Gas, Welding, Brazing, Cutting, Painting, Bending and Consumable Materials, Etc.						
				TOTAL ABC				
					TOTAL QUOTED AMOUNT IN WORDS:			

Reviewed and Checked By:

DONNABEL D. CAMUS
BAC TWG

91-2023

Please quote at your government price (including VAT) and state that the time within which you can make delivery. It will be appreciated if we can have your quotation in the office as soon as possible

Angel S. Ancheta
BUYER/ END-USER

TERMS AND CONDITIONS:

1. Price quotation/s shall be valid for a period of at least (30) calendar days from the date of submission.
2. In order to assure that manufacturing defects shall be corrected by supplier, a warranty security shall be required from the contract awardee for a minimum period of **three (3) months**, in the case of EXPENDABLE SUPPLIES, or a **minimum of one (1) year**
3. Delivery period within _____ calendar days
4. Award of contract shall be made to the lowest quotation wich complies with the technical specifications, and other terms and conditon stated herein
5. UPLB reserves the right to reject any or all offers as may be considered most advantageous to the University.
6. Any interlineations, erasure, or overwriting shall be valid only if they are signed or initiated by you or any of your duly authorized representative/s.

Requirements for Suppliers (GPPB Resolution No. 21-2017)

	REQUIREMENTS	Shopping	Negotiated	Negotiated	Negotiated Procurement- Scientific,	Negotiated
1	Mayor's/Business Permit	/	/	/	/	/
2	PhilGEPS Registration Number	/	/	/	/	/
3	Professional license/ CV (consulting services)		/		/	
4	PCAB License (for Infrastructure)		/			
5	Income / Business tax returns (except for government agencies as lessor)		FOR ABC'S ABOVE	/	/	FOR ABC'S
6	Omnibus Sworn Statement		FOR ABC'S ABOVE			FOR ABC'S
7	NFCC for Infrastructure with ABC above Ph500k		/			FOR ABC'S

After having carefully read and accepted your General Conditions. I/We quote you on the item at prices noted above.

Name of the Company: _____
Address: _____
_____
Signature over Printed Name of: _____
Position: _____

Tel. No: _____
Fax No: _____
Email Address: _____
Date: _____